

P.O. Box 460 (81502)
2190 H 1/4 Road
Grand Junction, CO 81505



Office: (970)242-7491
Fax: (970) 242-9189
www.utewater.org

ADDENDUM NO. 1
23 ROAD (H ROAD TO I ROAD) 8-INCH WATERLINE REPLACEMENT PROJECT

To all prospective **BIDDERS** for construction of the **23 ROAD (H ROAD TO I ROAD) 8-INCH WATERLINE REPLACEMENT PROJECT** for the Ute Water Conservancy District (District) for which BIDS are to be received until 2:00 PM, Thursday September 1, 2022 at the office of the District, 2190 H ¼ Road, Grand Junction, Colorado:

- 1) Schedule of Prices (Attached); removed Item 2b from the schedule, added the unit prices for which Item 3 will be paid, and added a new quantity for Item 4c.

Item 2b – Class II (gravel drives and shoulders), has been removed from the schedule.

Item 3 – Select Backfill Material as Directed by Engineer –

- a. Type A Material (aggregate base course) – 250 Tons @ \$24.00/Ton
- b. Type E Material (approved pit run) – 500 Tons @ \$20.00/Ton
- c. 1 ½” Screened Rock – 250 Tons @ \$25.00/Ton

Item 4 – Pipeline Trench Surface Restoration

- c. Class C (gravel shoulders and driveways) – 5,300 LF

This **ADDENDUM NOTICE NO. 1** is made effective this **31st day of August, 2022** and applies to the Plans, Specifications and Contract Documents identified above for the Ute Water Conservancy District.


Ute Water Conservancy District

Bidder must sign this ADDENDUM NOTICE NO. 1 and attach it to its submitted Bid.

Date: _____

Firm: _____

Official Address

By: _____

23 ROAD 8-INCH WATERLINE UPGRADE PROJECT (H TO I ROAD) SCHEDULE OF PRICES

Item	Description	Unit	Estimated Quantity	Unit Price	Total Price
1	Mobilization, Bonds, Permits, Insurance	LS	1		
2	Pipeline Trench Excavation and Backfill (Trench Detail, Sheet 15)				
	a. Class I (asphalt roads and driveways)	LF	5,481		
3*	Select Backfill Material as Directed by Engineer - Includes Removal and Disposal of Unsuitable Material from Required Excavation.				
	a. Type A Material (aggregate base course)	Ton	250	\$24.00	\$6,000.00
	b. Type E Material (approved pit run)	Ton	500	\$20.00	\$10,000.00
	c. 1 1/2" Screened Rock	Ton	250	\$25.00	\$6,250.00
4	Pipeline Trench Surface Restoration (Trench Detail, Sheet 15)				
	a. Asphalt Pavement (4-inch thickness) (Includes striping per Mesa County Specifications)	Ton	341		
	b. Asphalt Pavement Mill & Overlay (Includes striping per Mesa County Specifications)	Ton	200.0		
	c. Class C (gravel shoulders and driveways)	LF	5,300		
5	Pipeline and Fittings, in place - Includes all pipe, valves, fittings and appurtenances. DI Fittings and accessories shall be DOMESTIC .				
	8-inch C900 DR-18 PVC Pipe	LF	5,481		
6	Meter Service Connections - Includes all material, labor, and equipment necessary to relocate and connect to either existing water meter service lines or new water meter yokes. Includes surface restoration.				
	a. 1" service line (near side)	EA	2		
	b. 1" service line (far side)	EA	2		
	c. 3/4" service line (near side)	EA	11		
	d. 3/4" service line (far side)	EA	4		
7	New Fire Hydrant Installation- Includes trench excavation, backfill (Class I), surface restoration (asphalt), new hydrant, pipe, valve, fittings, and restraints. DI Fittings and accessories shall be DOMESTIC ., (Detail B, Sheet 15), (Lower Valley Fire District Hydrant including Storz Nozzle)	EA	5		
8	Service Line Connection at intersection fo 23 and I Roads - Includes all material, labor, and equipment necessary to connect 8-inch main to 2-inch service line. Including tee, valving, and all piping and fittings. Includes surface restoration.	LS	1		
9	Traffic Control - Adder for Flaggers as required for a portion of this work to manage one-way traffic as needed.	Day	30		
10	Potholing as Directed by the Engineer - Includes all equipment and labor for subsurface investigation.	HR	10		
Total					

* Item 3 (Engineer Directed Backfill) will be paid at the unit price listed in the Schedule of Prices.

This Bid was prepared for the below listed Contractor.

CONTRACTOR

Name:

Signature:

Title:

Date:
