

P.O. Box 460 (81502)
2190 H ¼ Road
Grand Junction, CO 81505



Office: (970)242-7491
Fax: (970) 242-9189
www.utewater.org

ADDENDUM NO. 1
Sundance Drive 6-inch Waterline Replacement Project: D01-26

11 August 2026

To all prospective **BIDDERS** for construction of the **SUNDANCE DRIVE 6-INCH WATERLINE REPLACEMENT PROJECT** for the Ute Water Conservancy District (District) for which BIDS are to be received until 2:00 PM, Thursday 20 August 2026 at the office of the District, 2190 H ¼ Road, Grand Junction, Colorado. Bidders responding to the above referenced solicitation are hereby instructed that the requirements have been clarified, modified, superseded, and supplemented as to this date as hereinafter described:

- 1) Schedule of Prices (attached in project documents on website); added unit pricing and total pricing for Items 3a-c (Select Backfill Material As Directed by Engineer), updated Asphalt Surface Restoration Quantities (Items 4a-b) to include cuts for temporary services and added detail to Item 4c (Concrete Driveway).

Item 3a – Type A Material (aggregate base course) at \$26.00 per Ton.

Item 3b – Type E Material (approved pit run) at \$21.50 per Ton.

Item 3c – 1 ½” Screened Rock at \$27.00 per Ton.

- 2) Revision 1 of the Bid Plans (attached in project documents on website) shows locations of potholes and respective depths to utilities, as well as the approximate locations of the road cuts associated with the temporary service lines. Asphalt patching for these cuts are included in the contract and Schedule of Values.

- 3) Please make note of the following questions and clarifications:

Q: Page 8, 10” casing---that casing is existing and the contractor is to connect to the existing 6” C900 carrier pipe? The casing/carrier is not a new item in this project?

A: The casing pipe was installed with carrier pipe by others as of March 2026. The carrier pipe was pressure tested, but will need to be part of the contractor’s Bacteriological testing. Contractor shall connect to both ends of the carrier pipe as part of this contract. Contractor

shall furnish and install cathodic protection to the existing casing pipe as it was missed back in March.

Q: Any chance of being emailed the list of prebid attendees?

A: The list of prebid attendees will be posted on the website (utewater.org) on the Current Projects page.

4) The Pre-Bid agenda and notes are attached on website on the Current Projects page.

This **ADDENDUM NOTICE NO. 1** is made effective **this 11th day of August 2026** and applies to the Plans, Specifications and Contract Documents identified above for the Ute Water Conservancy District.

Ute Water Conservancy District

Bidders must sign this ADDENDUM NOTICE NO. 1 and attach it to its submitted Bid.

Date: _____

Firm: _____

Official Address

By: _____
